Zone	Station Point	Linear Feet	Stabilization/ Revegetation Recommendation	Ownership Summary
12	N114+10 to 116+90	280	A or D	Private
13	N116+90 to 118+25	135	A or B	Private
14	N118+25 to 120+15	190	A	Private
15	N120+15 to 120+60	45	J	Private
16	N120+60 to 120+85	25	E and J	Private
17	N120+85 to 121+15	30	J	Private
18	N121+15 to 123+90	275	J (or A)	Private
19	N123+90 to 126+25	235	A or (D and B)	Private
20	N126+25 to 127+60	135	J (or A)	Private
21	N128+05 to 129+60	155	A or B	Private
22	N127+60 to 130+60	300	J	Private
23	S128+85 to 132+90	405	A or B	Private

Indicates a high priority stabilization project

Treatment Alternatives Key

A – No Action
B – Vegetation Only
C – Repair Protection
D – Vegetate Structure
E – Remove Structure
F – Regrade and Replant
G – Terrace
H – Riprap Toe
I – Vegetated Riprap
J – Vegetated Wall

3

BANK STABILIZATION AND REVEGETATION RECOMMENDATIONS

SAN FRANCISQUITO CREEK
BANK STABILIZATION & REVEGETATION
PRELIMINARY MASTER PLAN REPORT

Station: 114+00 to 130+00 May 12, 2000