Treatment Alternatives Key

A – No Action
B – Vegetation Only
C – Repair Protection
D – Vegetate Structure
E – Remove Structure
F – Regrade and Replant
G – Terrace
H – Riprap Toe
I – Vegetated Riprap
J – Vegetated Wall

Zone	Station Point	Linear Feet	Stabilization/ Revegetation Recommendation	Ownership Summary
58	S167+50 to 169+10	160	A or D	Palo Alto
59	N167+25 to 169+20	195	A	Private
60	N168+60 to 169+85	125	A or B	Private
61	S169+10 to 171+55	245	A or B	Palo Alto
62	N170+60 to 172+55	205	A	Private
63	N169+85 to 171+80	195	A or D	Private
64	S170+00 to 175+60	560	A	Palo Alto
65	N172+55 to 172+75	20	C	Private
66	N172+75 to 173+80	105	A (or J)	Private
67	N173+40 to 174+60	120	A or B	Private
68	S174+90 to 175+45	55	A or B	Palo Alto
69	N174+35 to 176+80	245	J (or A)	Private
70	N176+80 to 177+60	80	A	Private
71	S175+60 to 177+60	200	A or D	Palo Alto
72	N178+70 to 179+50	80	E and J	Menlo Park
73	S178+70 to 179+30	60	E and J	Palo Alto
74	S178+90 to 179+55	65	A or B	Palo Alto
75	S179+30 to 182+80	350	F, I, J, or A	Palo Alto
76	N179+45 to 180+00	55	A or B	Menlo Park
77	N179+75 to 180+25	50	A	Menlo Park
78	N180+00 to 181+00	100	A (or B)	Menlo Park
79	N181+00 to 184+10	310	J (or A)	Menlo Park
80	S182+60 to 183+00	40	A or B	Palo Alto

6

BANK STABILIZATION AND REVEGETATION RECOMMENDATIONS

SAN FRANCISQUITO CREEK
BANK STABILIZATION & REVEGETATION
PRELIMINARY MASTER PLAN REPORT

Station: 167+00 to 184+00 May 12, 2000